

OFFICIAL BID FORM

ITEM 00300

**2021 PAVING PROGRAM
Project ##5-2021**
Williams County, Ohio

Williams County Engineer's Office
12953 County Road G
Bryan, Ohio 43506
419-636-2454
Fax 419-636-8687
Todd J. Roth, P.E., P.S.
email: troth@wmscoengineer.com

Date: 03/25/21 Revised:
Prepared By: Clum
Revised By: Clum

Bid Date: Thursday, April 15, 2021 @ 10:00 AM

Bid Item	Item	Name	Unit	Quantity	Unit Price	Cost
COUNTY ROAD J						
County Road J, SR 576 to SR 15						
1	254	Pavement Planing, 1.5"	SY	20,583.0		
2	254	Pavement Planing, 2"	SY	14,902.0		
3	254	Pavement Planing, Full Depth Asphalt, 5" Maximum (AS DIRECTED)	SY	1,251.0		
4	301	Asphalt Concrete Base, PG 64-22 (AS DIRECTED)	CY	174.0		
5	407	Tack Coat	GAL	3,200.0		
6	411	Aggregate Berm	CY	193.0		
7	441	Asphalt Concrete Intermediate Type 1 (448)	CY	745.0		
8	SS823	Asphalt Concrete Surface Type 1, (448) PG64-22	CY	1,491.0		
9	614	Maintenance of Traffic	LS	1.0		
10	624	Mobilization	LS	1.0		
11	624	Premium for Contract Performance Bond	LS	1.0		
12	642	Pavement Striping, Type 1 (Centerline & Edgeline 4")	LS	1.0		
COUNTY ROAD C						
County Road C, SR 576 to CR 12/C						
13	254	Pavement Planing, 1.5"	SY	20,695.0		
14	254	Pavement Planing, Full Depth Asphalt, 5" Maximum (AS DIRECTED)	SY	1,897.0		
15	301	Asphalt Concrete Base, PG 64-22 (AS DIRECTED)	CY	263.0		
16	407	Tack Coat	GAL	1,863.0		
17	411	Aggregate Berm	CY	110.0		
18	441	Asphalt Concrete Intermediate Type 1 (448) 0.50"	CY	287.0		
19	SS823	Asphalt Concrete Surface Type 1, (448) PG64-22	CY	863.0		
20	614	Maintenance of Traffic	LS	1.0		
21	624	Mobilization	LS	1.0		
22	624	Premium for Contract Performance Bond	LS	1.0		
23	642	Pavement Striping, Type 1 (Centerline & Edgeline 4")	LS	1.0		
SPOT PAVE *Asphalt Prices for spot paving to include Tack Coat						
County Road Q & 13, US 20 to CR R, 1,847' x 19.50' x 1.50" and 9,347' x 6' x 1.25"						
24a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	383.00		
24b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
24c	103	Contract Performance Bond	LS	1.00		
24d	624	Mobilization	LS	1.00		

OFFICIAL BID FORM						ITEM 00300
County Road 2.50, CR A to CR C.60, 5,824' x 20' x 1.50" and 6,635' x 6.0' x 1.25"						
25a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	693.00		
25b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
25c	103	Contract Performance Bond	LS	1.00		
25d	624	Mobilization	LS	1.00		
County Road 23.50, CR C to SR 34, 1,343' x 19.0' x 1.50" and 1,115' x 6.0' x 1.25" *Springfield TWP has a portion below also						
26a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	144.00		
26b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
26c	103	Contract Performance Bond	LS	1.00		
26d	624	Mobilization	LS	1.00		
County Road 24, US 6 to CR C, 6,035' x 20.0' x 1.50" Surface and 4,837' x 20.0' x 0.50" Scratch						
27a	SS823	Asphalt Concrete Scratch Course-Light, Type 1 PG-64-22 (448)	CY	75.00		
27b	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	559.00		
27c	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
27d	103	Contract Performance Bond	LS	1.00		
27e	624	Mobilization	LS	1.00		
County Road P.50, SR 49 to CR 7, 4,496' x 20.0' x 1.50" and 16,021' x 6.0' x 1.25" and 1,753 x 20.0' x 0.50" Scratch						
28a	SS823	Asphalt Concrete Scratch Course-Light, Type 1 PG-64-22 (448)	CY	54.00		
28b	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	787.00		
28c	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
28d	103	Contract Performance Bond	LS	1.00		
28e	624	Mobilization	LS	1.00		
WILLIAMS COUNTY SUB TOTAL:						
CENTER TOWNSHIP WORK						
Camelot Subdivision - Sam Anna Drive, 750' x 20.0' x 1"						
29a	Special	Thinlay Asphalt Concrete Surface, Type MED, including Tack	CY	56.00		
29b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
29c	103	Contract Performance Bond	LS	1.00		
29d	624	Mobilization	LS	1.00		
CR F: 0.5 Mile West of SR 576 60' x 18' x 1.5"						
30a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	5.00		
30b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
30c	103	Contract Performance Bond	LS	1.00		
30d	624	Mobilization	LS	1.00		
CR 10: 0.1 Mile North of CR F 40' x 18' x 1.5"						
31a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	3.33		
31b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
31c	103	Contract Performance Bond	LS	1.00		
31d	624	Mobilization	LS	1.00		

OFFICIAL BID FORM						ITEM 00300
		CR E: 0.1 Mile East of CR 8 30' x 18' x 1.5"				
32a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	2.50		
32b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
32c	103	Contract Performance Bond	LS	1.00		
32d	624	Mobilization	LS	1.00		
CENTER TOWNSHIP SUB TOTAL:						
SPRINGFIELD TOWNSHIP WORK * To be done with Williams County's CR 23.50 work						
		TR 23.50 - TR B.50 to CR C, 2640' x 20.0' x 1.50" and 2,640' x 6.0' x 1.25"				
33a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	133.00		
33b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
33c	103	Contract Performance Bond	LS	1.00		
33d	624	Mobilization	LS	1.00		
SPRINGFIELD TOWNSHIP SUB TOTAL:						
TOTAL BASE BID						
ENGINEER WILL PRODUCE A FILLABLE BID FORM POSTED ON THE WILLIAMS COUNTY ENGINEERS WEB PAGE						
<p>The above quantities are estimated amounts only, the final quantities may be more or less than listed above. Williams County will pay for the actual amount of materials delivered to Williams County at the unit price listed above. ODOT asphalt index will NOT apply to this project. Asphalt Pricing for Spot Paving and Township work should include the cost of Tack Coats. The Project Will Be Awarded On The Total Base Bid.</p>						
BIDDER: _____						
BIDDER SIGNATURE _____			DATE _____			