

OFFICIAL BID FORM

ITEM 00300

**2022 PAVING PROGRAM**  
**Project #3-2022**  
 Williams County, Ohio

Williams County Engineer's Office  
 12953 County Road G  
 Bryan, Ohio 43506  
 419-636-2454  
 Fax 419-636-8687  
**Todd J. Roth, P.E., P.S.**  
 email: troth@wmscoengineer.com

Date: 03/01/22 Revised:  
 Prepared By: Waterston  
 Revised By:

**Bid Date: Thursday, March 24, 2022 @ 10:00 AM**

Bld Item	Item	Name	Unit	Quantity	Unit Price	Cost
<b>COUNTY ROAD I</b>						
<b>County Road I, SR 576 TO SR 15</b>						
1	254	Pavement Planing, 1.5"	SY	29,341.0		
2	254	Pavement Planing, 2"	SY	6,834.0		
3	254	Pavement Planing, Full Depth Asphalt, 5" Maximum (AS DIRECTED)	SY	4,693.3		
4	301	Asphalt Concrete Base, 5", PG 64-22 (AS DIRECTED)	CY	651.9		
5	407	Tack Coat	GAL	5,426.3		
6	411	Aggregate Berm	CY	382.3		
7	441	Asphalt Concrete Intermediate Type 1 (448)	CY	502.4		
8	SS823	Asphalt Concrete Surface Type 1, (448) PG64-22	CY	1,507.3		
9	614	Maintenance of Traffic	LS	1.0		
10	624	Mobilization	LS	1.0		
11	624	Premium for Contract Performance Bond	LS	1.0		
12	642	Pavement Striping, Type 1	LS	1.0		
<b>Willow Glenn Subdivision</b>						
<b>Willow Circle, off of CR 12.50</b>						
13a	Special	Thinlay Asphalt Concrete Surface, Type MED, including Tack	CY	55.00		
13b	614	Maintenance of Traffic	LS	1.00		
13c	103	Contract Performance Bond	LS	1.00		
13d	624	Mobilization	LS	1.00		
<b>SPOT PAVE *Asphalt Prices for spot paving to include Tack Coat</b>						
<b>County Roads A, 12, &amp; B.75, CR 10 to CR 13, 125' x 20' x 1.50", 2,451' x 19' x 1.50", 483' x 17.5' x 1.50" and 4,344' x 6.0' x 1.25"</b>						
14a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	356.00		
14b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
14c	103	Contract Performance Bond	LS	1.00		
14d	624	Mobilization	LS	1.00		
<b>County Road 9, CR A to CR G, 10,155' x 19.8' x 1.50" and 7,904' x 6.0' x 1.25"</b>						
15a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	1112.00		
15b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
15c	103	Contract Performance Bond	LS	1.00		
15d	624	Mobilization	LS	1.00		
<b>County Road E.75, SR 49 to CR 7, 5341' x 19.3' x 1.50" and 6,852' x 6.0' x 1.25"</b>						
16a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	636.00		
16b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		

OFFICIAL BID FORM					ITEM 00300
16c	103	Contract Performance Bond	LS	1.00	
16d	624	Mobilization	LS	1.00	
<b>County Road 22.75 + Stub Streets East, SR 2 to CR 21/N, 2,291' x 20.0' x 1.50" and 4,729' x 6.0' x 1.25"</b>					
17a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	321.00	
17b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00	
17c	103	Contract Performance Bond	LS	1.00	
17d	624	Mobilization	LS	1.00	
<b>County Road O, US 127 to CR 22, 1,240' x 20.0' x 1.50" and 2,310' x 6.0' x 1.25"</b>					
18a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	168.00	
18b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00	
18c	103	Contract Performance Bond	LS	1.00	
18d	624	Mobilization	LS	1.00	
<b>County Roads R,18, and S, CR 17 to CR 18, 1,894.4' x 20.0' x 1.50" and 2,988' x 6.0' x 1.25"</b>					
19a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	316.00	
19b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00	
19c	103	Contract Performance Bond	LS	1.00	
19d	624	Mobilization	LS	1.00	
<b>CENTER TOWNSHIP WORK</b>					
<b>Hickory Creek Subdivision - Turnberry Drive, 3290' x 19.0' x 1"</b>					
20a	Special	Thinlay Asphalt Concrete Surface, Type MED, including Tack	CY	193.00	
20b	254	Pavement Planning, 4' Front of curb	SY	2924.00	
20c	614	Maintenance of Traffic	LS	1.00	
20d	103	Contract Performance Bond	LS	1.00	
20e	624	Mobilization	LS	1.00	
<b>CR F: West of SR 34 138' x 9' x 1.5" Wedge, 138' x 19' x 1.5" Spot Pave</b>					
21a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	18.00	
21b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00	
21c	103	Contract Performance Bond	LS	1.00	
21d	624	Mobilization	LS	1.00	
<b>CR B: Between CR 7 &amp; CR 8 72' x 8' x 1.5" Wedge, 110' x 16' x 1.5" Spot Pave</b>					
22a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	11.00	
22b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00	
22c	103	Contract Performance Bond	LS	1.00	
22d	624	Mobilization	LS	1.00	
<b>CR E: East of CR 9 95' x 9' x 1.5" Wedge</b>					
23a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	4.00	
23b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00	
23c	103	Contract Performance Bond	LS	1.00	
23d	624	Mobilization	LS	1.00	
<b>CR 8: South of US 6 260' x 9' x 1.5" Wedge, 260' x 18' x 1.5" Spot Pave</b>					

<b>OFFICIAL BID FORM</b>					<b>ITEM 00300</b>
--------------------------	--	--	--	--	-------------------

24a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	33.00	
24b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00	
24c	103	Contract Performance Bond	LS	1.00	
24d	624	Mobilization	LS	1.00	

<b>TOTAL BASE BID</b>					
-----------------------	--	--	--	--	--

ENGINEER WILL PRODUCE A FILLABLE BID FORM POSTED ON THE WILLIAMS COUNTY ENGINEERS WEB PAGE

The above quantities are estimated amounts only, the final quantities may be more or less than listed above. Williams County will pay for the actual amount of materials delivered to Williams County at the unit price listed above. ODOT asphalt index will NOT apply to this project. Asphalt Pricing for Spot Paving and Township work should include the cost of Tack Coats. The Project Will Be Awarded On The Total Base Bid.

BIDDER: \_\_\_\_\_

\_\_\_\_\_  
BIDDER SIGNATURE

\_\_\_\_\_  
DATE