

WILLIAMS COUNTY OFFICIAL BID FORM - ITEM 00300

Project #3-2018 Williams County Commissioners / Williams County Engineer WIL-CR 202-2.18 BRIDGE REHABILITATION (03200 CR 2) PID 103664 Williams County, Ohio	WILLIAMS COUNTY ENGINEER'S OFFICE 12953 County Road G Bryan, OH 43506 Phone 419-636-2454 Fax 419-636-8687 Bid Opening: <u>March 19, 2018 @ 11:00 AM</u>
--	---

No.	Item	Description	Unit	Quantity	Unit Price	Cost
GROUP 0001: ROADWAY						
1.1	201E11000	CLEARING AND GRUBBING	LS	1		
1.2	202E23010	PAVEMENT REMOVED, ASPHALT	SY	431		
1.3	202E38000	GUARDRAIL REMOVED	FT	447		
1.4	230E10000	EXCAVATION	CY	171		
1.5	203E20000	EMBANKMENT	CY	44		
1.6	240E45000	PROOF ROLLING	HR	1		
1.7	606E15050	GUARDRAIL, TYPE MGS	FT	337.5		
1.8	606E35002	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	EA	4		
1.9	204E10000	SUBGRADE COMPACTION	SY	600		
TOTAL GROUP 0001: ROADWAY						
GROUP 0002: EROSION CONTROL						
2.1	601E32200	ROCK CHANNEL PROTECTION, TYPE C, WITH FILTER	CY	138		
2.2	659E10000	SEEDING AND MULCHING, INCLUDING FERTILIZER	LS	1		
2.3	832E30000	EROSION CONTROL	EA	1,000		
TOTAL GROUP 0002: EROSION CONTROL						
GROUP 0003: DRAINAGE						
3.1	605E31100	AGGREGATE DRAINS	FT	73		
TOTAL GROUP 0003: DRAINAGE						
GROUP 0004: PAVEMENT						
4.1	301E46000	ASPHALT CONCRETE BASE, PG64-22	CY	44		
4.2	304E10000	AGGREGATE BASE	CY	86		
4.3	407E10000	TACK COAT	GAL	48		
4.4	411E10000	STABILIZED CRUSHED AGGREGATE	CY	73		
4.5	441E50000	ASPHALT SURFACE COURSE, TYPE 1, (448) PG64-22	CY	32		
TOTAL GROUP 0004: PAVEMENT						
GROUP 0005: TRAFFIC CONTROL						
5.1	626E00102	BARRIER REFLECTORS	EA	8		
5.2	642E00090	EDGE LINE, AS PER PLAN	MILE	0.12		
5.3	642E00290	CENTER LINE, AS PER PLAN	MILE	0.06		
TOTAL GROUP 0005: TRAFFIC CONTROL						
GROUP 0006: STRUCTURE						
6.1	202E11203	PORTIONS OF STRUCTURE REMOVED, OVER 20' SPAN, AS PER PLAN	LS	1		
6.2	503E21300	UNCLASSIFIED EXCAVATION	LS	1		
6.3	509E10000	EPOXY COATED REINFORCING STEEL	LB	26,389		
6.4	510E10000	DOWEL HOLES WITH NONSHRINK, NONMETALIC GROUT	EA	40		
6.5	511E21521	CLASS QC2 CONCRETE, SUPERSTRUCTURE, AS PER PLAN	CY	120		

6.6		511E45711	CLASS QC1 CONCRETE, ABUTMENT, AS PER PLAN	CY	4			
6.7		512E10050	SEALING OF CONCRETE SURFACES (NON-EPOXY)	SY	93			
6.8		513E20000	WELDED STUD SHEAR CONNECTORS	EA	872			
6.9		514E00050	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	SF	3,670			
6.10		514E00056	FIELD PAINTING OF STRUCTURAL STEEL, PRIME COAT	SF	3,670			
6.11		514E00060	FIELD PAINTING OF STRUCTURAL STEEL, INTERMEDIATE COAT	SF	3,670			
6.12		514E00066	FIELD PAINTING OF STRUCTURAL STEEL, FINISH COAT	SF	3,670			
6.13		514E00504	GRINDING FINIS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL	MNHR	8			
6.14		514E10000	FINAL INSPECTIONS REPAIR	EA	6			
6.15		516E14020	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	FT	56			
6.16		516E44000	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), 1 3/8" X 7" X 13" PAD AND 1 1/2" X 8" X 14" LOAD PLATE	EA	8			
6.17		516E13900	2" PREFORMED EXPANSION JOINT FILLER	SF	22			
6.18		516E44000	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), 1" X 8" X 14" PAD AND 1 1/4" X 9" X 15" LOAD PLATE	EA	8			
6.19		516E47001	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	LS	1			
6.20		517E70000	RAILING (TWIN STEEL TUBE)	FT	238.63			
6.21		518E21100	POROUS BACKFILL WITH GEOTEXTILE FABRIC	LS	1			
6.22	SPECIAL	518E22300	STEEL DRIP STRIP	FT	247			
6.23		518E40000	6" PERFORATED CORRUGATED PLASTIC PIPE	FT	84			
6.24		518E40010	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	FT	40			
6.25		519E11100	PATCHING CONCRETE STRUCTURES	SF	50			
6.26		526E10000	REINFORCED CONCRETE APPROACH SLAB (T=12")	SY	94			
				TOTAL GROUP 0006: STRUCTURE				
				GROUP 0007: INCIDENTALS				
7.1		614E11000	MAINTAINING TRAFFIC	LS	1.000			
7.2		623E10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1.000			
7.3		624E10000	MOBILIZATION	LS	1.000			
				TOTAL GROUP 0007: INCIDENTALS				
				TOTAL BASE BID				
ENGINEER WILL PRODUCE A FILLABLE BID FORM FOR POSTING ON WMS CO WEB PAGE								
Submitted By:								

BIDDER								

SIGNATURE				Date				
END OF ITEM								