

WILLIAMS COUNTY OFFICIAL BID FORM - ITEM 00300

BIDDER

Project #3-2018 Williams County Commissioners / Williams County Engineer WIL-CR 202-2.18 BRIDGE REHABILITATION (03200 CR 2) PID 103664 Williams County, Ohio	WILLIAMS COUNTY ENGINEER'S OFFICE 12953 County Road G Bryan, OH 43506 Phone 419-636-2454 Fax 419-636-8687 Bid Opening: <u>TBD, 2018</u>	sample bidder USA anytown, USA
--	---	---

No.	Item	Description	Unit	Quantity	Unit Price	Cost	Unit Price	Cost
GROUP 0001: ROADWAY								
1.1	201E11000	CLEARING AND GRUBBING	LS	1				\$0.00
1.2	202E23010	PAVEMENT REMOVED, ASPHALT	SY	431				\$0.00
1.3	202E38000	GUARDRAIL REMOVED	FT	447				\$0.00
1.4	230E10000	EXCAVATION	CY	171				\$0.00
1.5	203E20000	EMBANKMENT	CY	44				\$0.00
1.6	240E45000	PROOF ROLLING	HR	1				\$0.00
1.7	606E15050	GUARDRAIL, TYPE MGS	FT	337.5				\$0.00
1.8	606E35002	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	EA	4				\$0.00
1.9	204E10000	SUBGRADE COMPACTION	SY	600				\$0.00
					TOTAL GROUP 0001: ROADWAY	\$28,155.82		\$0.00
GROUP 0002: EROSION CONTROL								
2.1	601E32200	ROCK CHANNEL PROTECTION, TYPE C, WITH FILTER	CY	138				\$0.00
2.2	659E10000	SEEDING AND MULCHING, INCLUDING FERTILIZER	LS	1				\$0.00
2.3	832E30000	EROSION CONTROL	EA	1,000				\$0.00
					TOTAL GROUP 0002: EROSION CONTROL	\$19,554.92		\$0.00
GROUP 0003: DRAINAGE								
3.1	605E31100	AGGREGATE DRAINS	FT	73				\$0.00
					TOTAL GROUP 0003: DRAINAGE	\$943.16		\$0.00
GROUP 0004: PAVEMENT								
4.1	301E46000	ASPHALT CONCRETE BASE, PG64-22	CY	44				\$0.00
4.2	304E10000	AGGREGATE BASE	CY	86				\$0.00
4.3	407E10000	TACK COAT	GAL	48				\$0.00
4.4	411E10000	STABILIZED CRUSHED AGGREGATE	CY	73				\$0.00
4.5	441E50000	ASPHALT SURFACE COURSE, TYPE 1, (448) PG64-22	CY	32				\$0.00
					TOTAL GROUP 0004: PAVEMENT	\$25,033.43		\$0.00
GROUP 0005: TRAFFIC CONTROL								
5.1	626E00102	BARRIER REFLECTORS	EA	8				\$0.00
5.2	642E00090	EDGE LINE, AS PER PLAN	MILE	0.12				\$0.00
5.3	642E00290	CENTER LINE, AS PER PLAN	MILE	0.06				\$0.00
					TOTAL GROUP 0005: TRAFFIC CONTROL	\$176.96		\$0.00
GROUP 0006: STRUCTURE								
6.1	202E11203	PORTIONS OF STRUCTURE REMOVED, OVER 20' SPAN, AS PER PLAN	LS	1				\$0.00
6.2	503E21300	UNCLASSIFIED EXCAVATION	LS	1				\$0.00
6.3	509E10000	EPOXY COATED REINFORCING STEEL	LB	26,389				\$0.00
6.4	510E10000	DOWEL HOLES WITH NONSHRINK, NONMETALIC GROUT	EA	40				\$0.00
6.5	511E21521	CLASS QC2 CONCRETE, SUPERSTRUCTURE, AS PER PLAN	CY	120				\$0.00

6.6		511E45711	CLASS QC1 CONCRETE, ABUTMENT, AS PER PLAN	CY	4			\$0.00
6.7		512E10050	SEALING OF CONCRETE SURFACES (NON-EPOXY)	SY	93			\$0.00
6.8		513E20000	WELDED STUD SHEAR CONNECTORS	EA	872			\$0.00
6.9		514E00050	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	SF	3,670			\$0.00
6.10		514E00056	FIELD PAINTING OF STRUCTURAL STEEL, PRIME COAT	SF	3,670			\$0.00
6.11		514E00060	FIELD PAINTING OF STRUCTURAL STEEL, INTERMEDIATE COAT	SF	3,670			\$0.00
6.12		514E00066	FIELD PAINTING OF STRUCTURAL STEEL, FINISH COAT	SF	3,670			\$0.00
6.13		514E00504	GRINDING FINNS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL	MNHR	8			\$0.00
6.14		514E10000	FINAL INSPECTIONS REPAIR	EA	6			\$0.00
6.15		516E14020	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	FT	56			\$0.00
6.16		516E44000	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), 1 3/8" X 7" X 13" PAD AND 1 1/2" X 8" X 14" LOAD PLATE	EA	8			\$0.00
6.17		516E13900	2" PREFORMED EXPANSION JOINT FILLER	SF	22			\$0.00
6.18		516E44000	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), 1" X 8" X 14" PAD AND 1 1/4" X 9" X 15" LOAD PLATE	EA	8			\$0.00
6.19		516E47001	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	LS	1			\$0.00
6.20		517E70000	RAILING (TWIN STEEL TUBE)	FT	238.63			\$0.00
6.21		518E21100	POROUS BACKFILL WITH GEOTEXTILE FABRIC	LS	1			\$0.00
6.22	SPECIAL	518E22300	STEEL DRIP STRIP	FT	247			\$0.00
6.23		518E40000	6" PERFORATED CORRUGATED PLASTIC PIPE	FT	84			\$0.00
6.24		518E40010	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	FT	40			\$0.00
6.25		519E11100	PATCHING CONCRETE STRUCTURES	SF	50			\$0.00
6.26		526E10000	REINFORCED CONCRETE APPROACH SLAB (T=12")	SY	94			\$0.00
						TOTAL GROUP 0006: STRUCTURE	\$433,885.40	\$0.00
						GROUP 0007: INCIDENTALS		
7.1		614E11000	MAINTAINING TRAFFIC	LS	1.000			\$0.00
7.2		623E10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1.000			\$0.00
7.3		624E10000	MOBILIZATION	LS	1.000			\$0.00
						TOTAL GROUP 0007: INCIDENTALS	\$21,500.00	\$0.00
CONSTRUCTION ESTIMATE		\$529,249.69				TOTAL BASE BID	\$0.00	