

WILLIAMS COUNTY OFFICIAL BID FORM - ITEM 00300

Project #1-2019 Williams County Commissioners / Williams County Engineer WIL-TR198-16.35 BRIDGE REPLACEMENT 16350 TR F.75 PID 107159 Williams County, Ohio	WILLIAMS COUNTY ENGINEER'S OFFICE 12953 County Road G Bryan, OH 43506 Phone 419-636-2454 Fax 419-636-8687 Bid Opening: <u>April 18, 2019 @ 11:00 AM</u> As Revised By Addendum 1
---	---

No.	Item	Description	Unit	Quantity	Unit Price	Cost
GROUP 0001: ROADWAY						
1-1	0001	201E11001	CLEARING AND GRUBBING. AS PER PLAN	LS	1	
1-2	0002	202E21800	TREE REMOVED, 18 INCH	EA	4	
1-3	0003	202E23010	PAVEMENT REMOVED, ASPHALT	SY	447	
1-4	0004	202E35100	PIPE REMOVED, 24" AND UNDER	FT	79	
1-5	0005	202E38000	GUARDRAIL REMOVED	FT	32	
1-6	0006	230E10000	EXCAVATION	CY	511	
1-7	0007	203E20000	EMBANKMENT	CY	94	
1-8	0008	204E10000	SUBGRADE COMPACTION	SY	571	
1-9	0009	240E45000	PROOF ROLLING	HR	1	
1-10	0010	606E15100	GUARDRAIL, TYPE MGS WITH LONG POSTS	FT	25.0	
1-11	0011	606E25550	ANCHOR ASSEMBLY, MGS TYPE A	EA	2	
1-12	0012	606E26550	ANCHOR ASSEMBLY, MGS TYPE T	EA	2	
1-13	0013	606E35003	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1, AS PER PLAN	EA	4	
TOTAL GROUP 0001: ROADWAY						
GROUP 0002: EROSION CONTROL						
2-1	0014	601E21050	TIED CONCRETE BLOCK MAT, TYPE 1	SY	2	
2-2	0015	601E32210	ROCK CHANNEL PROTECTION, TYPE C, WITH AGGREGATE FILTER	CY	226	
2-3	0016	659E00300	TOPSOIL	CY	78	
2-4	0017	659E10000	SEEDING AND MULCHING	SY	704	
2-5	0018	659E14000	REPAIR SEEDING AND MULCHING	SY	35	
2-6	0019	659E15000	INTER-SEEDING	SY	35	
2-7	0020	659E20000	COMMERCIAL FERTILIZER	TON	0.10	
2-8	0021	659E31000	LIME	ACRE	0.15	
2-9	0022	659E35000	WATER	MGAL	4	
2-10	0023	832E30000	EROSION CONTROL	EA	7,000	
TOTAL GROUP 0002: EROSION CONTROL						
GROUP 0003: DRAINAGE						
3-1	0024	605E14000	6" BASE PIPE UNDERDRAINS	FT	192	
3-2	0025	605E31100	AGGREGATE DRAINS	FT	23	
3-3	0026	611E00510	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	FT	32	
3-4	0027	611E01400	6" CONDUIT, TYPE E	FT	50	
3-5	0028	611E01500	6" CONDUIT, TYPE F	FT	50	
3-6	0029	611E02600	8" CONDUIT, TYPE F	FT	50	
3-7	0030	611E04400	12" COUDUIT, TYPE B	FT	50	
3-8	0031	611E05200	12' CONDUIT, TYPE F	FT	43	
3-9	0032	611E99710	PRECAST REINFORCED CONCRETE OUTLET	EA	2	

3-10	0033	613E41201	LOW STRENGTH MORTAR BACKFILL, AS PER PLAN	CY	113		
TOTAL GROUP 0003: DRAINAGE							
GROUP 0004: PAVEMENT							
4-1	0034	301E46000	ASPHALT CONCRETE BASE, PG64-22	CY	57		
4-2	0035	304E20000	AGGREGATE BASE	CY	90		
4-3	0036	407E10000	TACK COAT	GAL	55		
4-4	0037	411E10000	STABILIZED CRUSHED AGGREGATE	CY	13		
4-5	0038	441E50000	ASPHALT SURFACE COURSE, TYPE 1, (448) PG64-22	CY	42		
TOTAL GROUP 0004: PAVEMENT							
GROUP 0005: SANITARY SEWER							
5-1	0039	611E01101	6" CONDUIT, TYPE C, AS PER PLAN	FT	50.00		
TOTAL GROUP 0005: SANITARY SEWER							
GROUP 0006: TRAFFIC CONTROL							
6-1	0040	626E00102	BARRIER REFLECTOR, TYPE 1 (BIDIRECTIONAL)	EA	2		
6-2	0041	626E00110	BARRIER REFLECTOR, TYPE 2 (BIDIRECTIONAL)	EA	4		
6-3	0042	630E03100	GROUND MOUNTED SUPPORT, NO. 3 POST	FT	24		
6-4	0043	630E08600	SIGN POST REFLECTOR	EA	1		
6-5	0044	630E85100	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	EA	2		
6-6	0045	630E86002	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	EA	2		
6-7	0046	642E00290	CENTER LINE	MILE	0.06		
TOTAL GROUP 0006: TRAFFIC CONTROL							
GROUP 0007: STRUCTURE OVER 20 FOOT SPAN (WIL-T.R. 198-16.35)							
7-1	0047	202E11003	STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LS	1		
7-2	0048	202E23500	WEARING COURSE REMOVED	SY	218		
7-3	0049	503E11100	COFFERDAMS AND EXCAVATION BRACING	LS	1		
7-4	0050	503E21301	UNCLASSIFIED EXCAVATION, AS PER PLAN	LS	1		
7-5	0051	505E11100	PILE DRIVING EQUIPMENT MOBILIZATION	LS	1		
7-6	0052	507E00600	14" CAST IN PLACE REINFORCED CONCRETE PILES, DRIVEN	FT	560		
7-7	0053	507E00650	14" CAST IN PLACE REINFORCED CONCRETE PILES, FURNISHED	FT	630		
7-8	0054	509E10000	EPOXY COATED REINFORCING STEEL	LB	14,915		
7-9	0055	511E31610	CLASS QC2 CONCRETE, SUPERSTRUCTURE	CY	65		
7-10	0056	511E43510	CLASS QC1 CONCRETE, ABUTMENT INCLUDING FOOTING	CY	75		
7-11	0057	512E10100	SEALING OF CONCRETE SURFACES (EXPOXY-URETHANE)	SY	128		
7-12	0058	515E12091	PRESTRESSED CONCRETE COMPOSITE BOX BEAM BRIDGE MEMBERS, LEVEL 1, CB33-48, AS PER PLAN (81'-0 3/8")	EA	7		
7-13	0059	516E13200	1/2" PREFORMED EXPANSION JOINT FILLER	SF	43		
7-14	0060	516E14014	INTEGRAL ABUTMENT EXPANSION JOINT SEAL	FT	18		
7-15	0061	516E20010	1' ELASTOMERIC ERECTION STRIP	SF	57		
7-16	0062	516E31011	2" DEEP JOINT SEALER, AS PER PLAN	FT	57		
7-17	0063	517E70000	RAILING TWIN STEEL TUBE	FT	172		
7-18	0064	518E21230	POROUS BACKFILL WITH GEOTEXTILE FABRIC	LS	1		
7-19	0065	518E22300	SPECIAL - STEEL DRIP STRIP	FT	192		
7-20	0066	518E40000	6" PERFORATED CORRUGATED PLASTIC PIPE	FT	66		
7-21	0067	518E40010	6" NON PERFORATED CORRUGATED PLASTIC PIPE, INCL SPECIALS	FT	56		
7-22	0068	523E20000	DYNAMIC LOAD TESTING	EA	1		
TOTAL GROUP 0007: STRUCTURE							

GROUP 0008: MAINTENANCE OF TRAFFIC						
8-1	0069	616E10000	WATER	MGAL	1.000	
TOTAL GROUP 0008: MAINTENANCE OF TRAFFIC						
GROUP 0009: INCIDENTALS						
9-1	0070	614E11000	MAINTAINING TRAFFIC	LS	1.000	
9-2	0071	619E16010	FIELD OFFICE, TYPE B	MNTH	3.000	
9-3	0072	623E10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1.000	
9-4	0073	624E10000	MOBILIZATION	LS	1.000	
TOTAL GROUP 0009: INCIDENTALS						
TOTAL BASE BID						
PLEASE NOTE: WILLIAMS COUNTY WILL PRODUCE A FILLABLE BID FORM AND POST ON THE ENGINEERS WEB PAGE						
Submitted By: _____						
BIDDER _____						
SIGNATURE _____			Date _____			
END OF ITEM						