OFFICIAL BID FORM

Item 00300

Project #2-2022
BRUCE DRIVE
RESURFACE/TURNAROUND
ROAD IMPROVEMENTS
Williams County, Ohio

Date: 2/08/2022 By:

Williams County Engineer's Office
12953 County Road G
Bryan, Ohio 43506
419-636-2454
Fax 419-636-8687
Todd J. Roth, P.E.,P.S.
email: troth@wmscoengineer.com

Revised: **BID Date: MARCH 14, 2022**

Bid Item	Item	Name	Unit	Quantity	Unit Price	Cost
		ROADWAY				
1	201	CLEARING AND GRUBBING	LUMP	1		
2	203	EXCAVATION	CU YD	117		
3	204	SUBGRADE COMPACTION	SQ YD	348		
4	254	BUTT JOINT	EACH	1		
5	304	12" AGGREGATE BASE	CU YD	134		
6	411	AGGREGATE BERM	CU YD	28		
7	452	6" CONCRETE DRIVE REPAIR	SQ YD	36		
		PAVEMENT				
8	SS823	1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1(448)	CU YD	68		
9	407	TACK COAT	GALLON	155		
10	441	1/2" ASPHALT CONCRETE SCRATCH COURSE, TYPE 1(448)	CU YD	20		
11	441	2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1(448)	CU YD	21		
		EROSION CONTROL				
12	SPEC	PERMITER FILTER FABRIC FENCE	FT	280		
13	SPEC	DANDY BAG	EACH	5		
14	659	SEEDING AND MULCHING	SQ YD	524		
		MISCELLANEOUS				
15	SPEC	DITCH GRADING	FT	472		
16	611	LOWERING OF YARD DRAINAGE INLET	EACH	1		
17	614	TRAFFIC MAINTENANCE	LUMP	1		
18	624	MOBILIZATION	LUMP	1		
19	SPEC	PREMIUM FOR CONTRACT PERFORMANCE BOND	LUMP	1		
					TOTAL BASE BID	

IT IS THE OWNERS INTENT THAT ALL WORK REQUIRED IN THE BID OR SPECICATIONS BE INCLUDED IN THE TOTAL BASE BID. IF AN ITEM IS REQUIRED TO COMPLETE THE WORK, BUT IS NOT SPECIFICALLY LISTED ABOVE, THE CONTRACTOR SHALL INCLUDE THE COST OF THAT ITEM IN OTHER BID ITEMS.

ODOT ASPHALT INDEX WILL NOT APPLY

END OF ITEM

BIDDER SIGNATURE Date: