

OFFICIAL BID FORM						ITEM 00300
<b>2020 COUNTY ROAD J AND SPOT PAVING PROJECT #5-2020</b> Williams County, Ohio				Williams County Engineer's Office 12953 County Road G Bryan, Ohio 43506 419-636-2454 419-636-8687 <b>Todd J. Roth, P.E., P.S.</b> email: troth@wmscoengineer.com		
Date: 04/08/2020		Revised:		<b>As Revised By Addendum 1</b>		
Prepared By: Clum				<b>Bid Date: Thursday, May 7, 2020 @ 10:00 AM</b>		
Revised By: Clum						
Bid Item	Item	Name	Unit	Quantity	Unit Price	Cost
<b>COUNTY ROAD J</b>						
<b>County Road J, CR 7 to CR 10</b>						
1	254	Pavement Planing, 1.5"	SY	19,782.0		
2	254	Pavement Planing, 2"	SY	19,284.0		
3	254	Pavement Planing, Full Depth Asphalt, 6" Maximum (AS DIRECTED)	SY	1,779.0		
4	301	Asphalt Concrete Base, PG 64-22 (AS DIRECTED)	CY	297.0		
5	407	Tack Coat	GAL	5,860.0		
6	411	Aggregate Berm	CY	119.0		
7	441	Asphalt Concrete Intermediate Type 1 (448)	CY	811.0		
8	SS823	Asphalt Concrete Surface Type 1, (448) PG64-22	CY	1,899.0		
9	614	Maintenance of Traffic	LS	1.0		
10	624	Mobilization	LS	1.0		
11	624	Premium for Contract Performance Bond	LS	1.0		
12	642	Pavement Striping, Type 1	LS	1.0		
<b>SPOT PAVE</b>						
<b>County Road A, SR 66 to CR 25, 5280' x 20' x 1.25" and .50" Scratch</b>						
13a	SS823	Asphalt Concrete Scratch Course-Light, Type 1 PG-64-22 (448)	CY	163.00		
13b	SS824	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	407.00		
13c	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
13d	103	Contract Performance Bond	LS	1.00		
13e	624	Mobilization	LS	1.00		
<b>County Road 19.50, CR G to CR I.50, 5550' x 19.0' x 1.50" and 10940' x 6.0' x 1.25"</b>						
14a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	741.00		
14b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
14c	103	Contract Performance Bond	LS	1.00		
14d	624	Mobilization	LS	1.00		
<b>County Road 8, US20 to County Line, 3834' x 19.0' x 1.50" and 22057' x 6.0' x 1.25"</b>						
15a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	848.00		
15b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
15c	103	Contract Performance Bond	LS	1.00		
15d	624	Mobilization	LS	1.00		

OFFICIAL BID FORM						ITEM 00300
County Road 4 & N.30, US 20 to SR 576, 7648' x 20.0' x 1.50" and 17848' x 6.0' x 1.25"						
16a	SS823	Asphalt Concrete Surface Course-Light, Type 1 PG-64-22 (448)	CY	1121.00		
16b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
16c	103	Contract Performance Bond	LS	1.00		
16d	624	Mobilization	LS	1.00		
WILLIAMS COUNTY SUB TOTAL						
CENTER TOWNSHIP WORK						
Sunrise Subdivision - Sunrise Lane, 2321' x 20.0' x 1"						
17a	Special	Thinlay Asphalt Concrete Surface, Type MED	CY	171.00		
17b	614	Maintenance of Traffic - Includes Temp Centerline (Tape) As Needed	LS	1.00		
17c	103	Contract Performance Bond	LS	1.00		
17d	624	Mobilization	LS	1.00		
CENTER TOWNSHIP SUB TOTAL						
<b>TOTAL BASE BID</b>						
ENGINEER WILL PRODUCE A FILLABLE BID FORM POSTED ON THE WMS CO ENGINEER'S WEB PAGE						
<p>The above quantities are estimated amounts only, the final quantities may be more or less than listed above. Williams County will pay for the actual amount of materials delivered to Williams County at the unit price listed above. ODOT asphalt index will NOT apply to this project. The Project Will Be Awarded On The Total Base Bid. Asphalt Pricing should include the cost of Tack Coats on Items 13a, 13b, 14a, 15a, 16a, and 17a. @ the rate of .09 gal/SY</p>						
<p>BIDDER: _____</p> <p>_____ Date _____</p> <p style="text-align: right;">END OF ITEM</p>						