

WILLIAMS COUNTY OFFICIAL BID FORM - ITEM 00300

Project #2-2017 Williams County Commissioners / Williams County Engineer	WILLIAMS COUNTY ENGINEER'S OFFICE 12953 County Road G Bryan, OH 43506 Phone 419-636-2454 Fax 419-636-8687
WIL-CR/TR-21N/M/M50 TURNPIKE MITIGATION ASPHALT PAVING AND BRIDGE REPLACEMENT 22760 CR M.50 PID 102067 Williams County, Ohio	Bid Opening: May 18, 2017

No.	Item	Description	Unit	Quantity	Unit Price	Cost
GROUP 0001: ROADWAY						Page 1 of 2
1.1	0005	201E11000	CLEANING AND GRUBBING	LS	1.000	
1.2	0006	202E38000	GUARDRAIL REMOVED	FT	387.500	
1.3	0007	204E10000	SUBGRADE COMPACTION	SY	797.000	
1.4	0008	606E15050	GUARDRAIL, TYPE MGS	FT	1,050.000	
1.5	0007	606E25550	ANCHOR ASSEMBLY, MGS TYPE A	EACH	12.000	
TOTAL GROUP 0001: ROADWAY						
GROUP 0002: EROSION CONTROL						
2.1	0010	832E30000	EROSION CONTROL	EACH	2,100.000	
TOTAL GROUP 0002: EROSION CONTROL						
GROUP 0003: PAVEMENT						
3.1	0011	253E02000	PAVEMENT REPAIR	CY	100.000	
3.2	0012	301E46000	ASPHALT CONCRETE BASE, PG64-22	CY	100.000	
3.3	0013	304E20000	AGGREGATE BASE	CY	145.000	
3.4	0014	305E11010	7" CONCRETE BASE, CLASS QC1	SY	162.000	
3.5	0015	407E10000	TACK COAT	GAL	7,603.000	
3.6	0016	441E50000	ASPHALT CONCRETE SURFACE COURSE TYPE 1 (448), PG64-22	CY	2,113.000	
3.7	0017	441E50200	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448)	CY	1,390.000	
3.8	0018	617E10100	COMPACTED AGGREGATE	CY	730.000	
3.9	0019	617E20000	SHOULDER PREPARATION	SY	8,589.000	
TOTAL GROUP 0003: PAVEMENT						
GROUP 0004: TRAFFIC CONTROL						
4.1	0020	626E00100	BARRIER REFLECTOR	EACH	25.000	
4.2	0021	630E84900	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	EACH	2.000	
4.3	0022	642E00090	EDGE LINE, 4"	MILE	3.020	
4.4	0023	642E00290	CENTER LINE	MILE	4.860	
TOTAL GROUP 0004: TRAFFIC CONTROL						
GROUP 0005: STRUCTURE OVER 20 FOOT SPAN (M.50 OVER BATES CREEK)						
5.1	0024	202E11002	STRUCTURE REMOVED, OVER 20 FOOT SPAN	LS	1.000	
5.2	0025	202E23500	WEARING COURSE REMOVED	SY	47.000	
5.3	0026	304E20001	AGGREGATE BASE, AS PER PLAN	CY	255.000	
5.4	0027	503E11100	COFFERDAMS AND EXCAVATION BRACING	LS	1.000	
5.5	0028	503E21100	UNCLASSIFIED EXCAVATION	CY	274.000	
5.6	0029	509E10000	EPOXY COATED REINFORCING STEEL	LB	8,070.000	
5.7	0030	511E44112	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT NOT INCLUDING FOOTING	CY	16.000	
5.8	0031	511E46512	CLASS QC1 CONCRETE WITH QC/QA, FOOTING	CY	40.000	
5.9	0032	512E10050	SEALING OF CONCRETE SURFACES (NON-EXPOXY)	SY	38.000	
5.10	0033	518E21200	POROUS BACKFILL WITH GEOTEXTILE FABRIC	CY	49.000	
5.11	0034	518E40000	6" PERFORATED CORRUGATED PLASTIC PIPE	FT	100.000	
5.12	0035	518E40010	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	FT	25.000	
5.13	0036	601E32204	ROCK CHANNEL PROTECTION, TYPE C WITH GEOTEXTILE FABRIC	CY	87.000	
5.14	0037	611E97300	CONDUIT, MISC.	LS	1.000	
TOTAL GROUP 0005: STRUCTURE OVER 20' SPAN						

		GROUP 0006: MAINTENANCE OF TRAFFIC				Page 2 of 2		
6.1	0038	614E12500	REPLACEMENT SIGN	EACH	5.000			
6.2	0039	614E12600	REPLACEMENT DRUM	EACH	25.000			
6.3	0040	616E10000	WATER	MGAL	3.000			
			TOTAL GROUP 0006: MAINTENANCE OF TRAFFIC					
		GROUP 0007: INCIDENTALS						
7.1	0041	614E11000	MAINTAINING TRAFFIC	LS	1.000			
7.2	0042	623E10000	CONSTRUCTION LAYOUT STAKING AND SURVEYING	LS	1.000			
7.3	0043	624E10000	MOBILIZATION	LS	1.000			
			TOTAL GROUP 0007: INCIDENTALS					
TOTAL BASE BID								
Submitted By: _____								
BIDDER _____								
SIGNATURE _____				Date _____				
END OF ITEM								