

OFFICIAL BID FORM

Item 00300

Project # 10-2016
WABASH-CANNONBALL TRAIL CONNECTOR
CITF-301
 Montpelier, Ohio

Village of Montpelier
 211 North Jonesville Street
 Montpelier, Ohio 43543
 419-485-5543
 Jason Rockey, Village Manager

Date: 2/25/21 Revised:

Prepared By: Clum 2-25-21

Revised By: **As Revised By Addendum 1**

Bid Date: April 28, 2021 @ 2:00 PM

Bid Item	Item	Name	Unit	Quantity	Unit Price	COST
APHALT PATH: 10' WIDE, FROM SR 107 TO WABASH CANNONBALL TRAIL						
Page 1 of 1						
ROADWAY						
1	201	CLEARING AND GRUBBING	LUMP	1		
2	203	EXCAVATION	CY	285		
3	203	EMBANKMENT	CY	42		
4	204	SUBGRADE COMPACTION	SY	1344		
PAVEMENT						
5	304	6" AGGREGATE BASE	CY	224		
6	407	TACK COAT	GAL	80		
7	408	PRIME COAT	GAL	270		
8	441	2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1 PG-64-22*	CY	68		
9	SS823	1.5" ASPHALT CONCRETE SURFACE COURSE-LIGHT, TYPE 1 PG 64-22*	CY	51		
10	451	NON-REINFORCED CONCRETE PAVEMENT CLASS 1 - 8 INCH (Includes 8" Non Reinforced Concrete on 6" 304 Base)	SY	19		
11	452	NON-REINFORCED CONCRETE PAVEMENT CLASS 1	SY	7		
DRAINAGE						
12	611	12" CONDUIT TYPE B	LF	63		
13	611	CATCH BASIN 2-2-B	EA	1		
14	611	CATCH BASIN RISER W/ GRATE	EA	4		
15	611	CATCH BASIN ADJUSTED TO GRADE W/ SOLID TOP	EA	1		
16	611	CATCH BASIN ADJUSTED TO GRADE W/ SLANTED TOP	EA	2		
17	611	MANHOLE ADJUSTED TO GRADE	EA	2		
18	611	12"X12" TEE EXISTING STORM CONNECTION	EA	2		
EROSION CONTROL						
19	659	SEEDING AND MULCHING	SY	1222		
MISCELLANEOUS						
20	614	MAINTAINING TRAFFIC	LS	1		
21	624	MOBILIZATION	LS	1		
22	Spec	PREMIUM FOR BOND	LS	1		

Total Base Bid

THE ABOVE QUANTITIES ARE ESTIMATED AMOUNTS ONLY, THE FINAL QUANTITIES MAY BE MORE OR LESS THAN LISTED ABOVE. THE OWNER WILL PAY FOR THE ACTUAL AMOUNT OF WORK AT THE WORK SITE AT THE UNIT PRICE LISTED ABOVE. ODOT ASPHALT INDEX WILL NOT APPLY TO THIS PROJECT. THE PROJECT WILL BE AWARDED ON THE TOTAL BASE BID.

BIDDER: _____

BIDDER SIGNATURE: _____ DATE: _____

END OF ITEM